

Sundance Estates

an Addition to the City of Lubbock, Lubbock County, Texas

Final Plat
Lots 62-111

KNOW ALL MEN BY THESE PRESENTS

That I, JONATHAN MARK CIESZINSKI, Registered Professional Land Surveyor do hereby certify that I prepared this plat from an actual and accurate survey of the land and the corner monuments shown thereon were properly placed under my personal supervision in accordance with the Subdivision Regulations of the City of Lubbock, Texas.



Jonathan Mark Cieszinski
REGISTERED PROFESSIONAL LAND SURVEYOR, # 4460 LUBBOCK, TEXAS
May 10, 2019
Revised October 12, 2020 (SPEC Easements, Perimeter, Adjoining Owners)
Revised November 5, 2020 (Changed lota to Huron)

CONTAINS 32.89 ACRES WITHIN THE PLAT LIMITS


- ALL ALLEYS ARE 20' IN WIDTH
- LPL - LUBBOCK POWER, LIGHT AND WATER CO.
 - AT&T - AT&T TELEPHONE COMPANY
 - UUE - UNDERGROUND UTILITY EASEMENT
 - EASEMENT
 - PVT - PRIVATE
 - TP - TRANSFORMER PAD EASEMENT, 4' X 6' (NOT DRAWN TO SCALE)
 - SWBT - SOUTHWESTERN BELL TELEPHONE CO.
 - WLE - WATER LINE EASEMENT
 - DRE - DRAINAGE EASEMENT
 - DUE - DRE and UUE CENTERED ON LOT LINE WHERE APPLICABLE
 - USE - UNDERGROUND STREET LIGHT CABLE EASEMENT
 - ACE - 5' ACCESS EASEMENT AND 2' EAVE OVERHANG EASEMENT
 - PAE - PEDESTRIAN ACCESS EASEMENT
 - SEE - SWITCH ENCLOSURE EASEMENT, 6' X 6' (NOT DRAWN TO SCALE)
 - CCFN - LUBBOCK COUNTY CLERK FILE NUMBER

A METES AND BOUNDS DESCRIPTION OF THIS TRACT WAS PREPARED FOR RECORDATION WITH THE DEDICATION DEED OF THIS TRACT.

Survey Control: Bearings and Coordinates are based on the Texas North Central Zone Coordinate System, NAD 83, 2011, EPOCH 2010.0000. Coordinates determined by OPUS Observations.

Any easements or rights-of-way shown as to be dedicated by separate instrument are shown on this plat for information purposes only. This plat does not dedicate said easements.

1/2" Iron Rod with Green Cap marked RPLS 4460 found or set at all block corners and control points.



APPROVED this July Day of 2nd, 2019, by the
PLANNING AND ZONING COMMISSION OF THE CITY OF LUBBOCK

APPROVED *[Signature]* CHAIRMAN

ATTEST *[Signature]* SECRETARY

SCALE: 1"=100'
HEAVY LINES INDICATE PLAT LIMITS.
ALL STREETS, ALLEYS, AND EASEMENTS WITHIN PLAT LIMITS ARE HEREIN DEDICATED.
ALL EASEMENTS DEDICATED HEREBY SHALL ENTITLE THE CITY OR THE UTILITY COMPANY USING SUCH EASEMENTS TO THE RIGHT TO REMOVE, REPAIR, OR REPLACE ANY LINES, PIPES, CONDUITS, OR POLES WITHIN SUCH EASEMENTS AS MAY BE DETERMINED BY THE CITY OR THE UTILITY COMPANY WITHOUT THE CITY OR THE UTILITY COMPANY BEING RESPONSIBLE OR LIABLE FOR THE REPLACEMENT OF IMPROVEMENTS, PAVING, OR SURFACING OF THE EASEMENT NECESSITATED BY SUCH REMOVAL, REPAIR, OR REPLACEMENT. EASEMENTS DESIGNATED OR INTENDED FOR VEHICULAR PASSAGE (UTILITY AND EMERGENCY) OR PEDESTRIAN ACCESS SHALL NOT BE FENCED OR OTHERWISE OBSTRUCTED.
ALL ELECTRICAL SERVICE SHALL BE IN ACCORDANCE WITH THE UNDERGROUND UTILITIES POLICY STATEMENT BY THE PLANNING AND ZONING COMMISSION OF THE CITY OF LUBBOCK, TEXAS.
ANY RELOCATION OR REVISION OF EXISTING FACILITIES SHALL BE AT THE DEVELOPER'S EXPENSE. COMPENSATION SHALL BE MADE PRIOR TO RECORDING OF ANY PORTION OF THIS PLAT.
ALL EXISTING OR PROPOSED UTILITY SERVICES TO AND ON TRACTS INDICATED BY THIS PLAT SHALL BE CONTAINED IN THE PUBLIC RIGHT-OF-WAY AND PUBLIC OR PRIVATE UTILITY EASEMENTS. UTILITY SERVICE INSTALLATION REQUESTED AT A FUTURE DATE, AND NOT WITHIN AN EASEMENT INDICATED BY THIS PLAT, SHALL BE WITHIN A PROPER UTILITY EASEMENT GRANTED BY THE OWNER OF SAID PROPERTY BY SEPARATE RECORDED INSTRUMENT PRIOR TO THE PROVISION OF SUCH SERVICE. SUCH EASEMENTS SHALL BE AT THE DEVELOPER'S EXPENSE.
NO BUILDING PERMIT SHALL BE ISSUED ON ANY SURVEY CERTIFICATE THAT IS NOT IN ACCORDANCE WITH AN APPROVED FINAL PLAT UNLESS AN EXCEPTION IS PROVIDED BY PLANNING COMMISSION POLICY OR BY THE LUBBOCK CODE OF ORDINANCES.
MINIMUM FINISH FLOOR SHALL CONFORM TO THE REQUIREMENTS OF THE LUBBOCK DRAINAGE CRITERIA MANUAL, AS ADOPTED BY RESOLUTION NO. 10022, AND SECTION 28.09.131, SECTION 28.14.004 AND SECTION 30.03.073 OF THE LUBBOCK CODE OF ORDINANCES.

ABACUS ENGINEERING SURVEYING
2737 81st Street
LUBBOCK, TEXAS
806-745-7670
Count on It

TEXAS SURVEYING FIRM NO. 101159-00
TEXAS ENGINEERING FIRM NO. 4366